



मादी गाउँपालिका

गाउँ कार्यपालिकाको कार्यालय

थुमाकोडाँडा, कास्की

गण्डकी प्रदेश, नेपाल

आ.व. २०८१/०८२

सूचना न.०१ (प्राविधिक शाखा)

कोटेशन पेश गर्ने सम्बन्धी सूचना।

प्रथम पटक प्रकाशित मिति: २०८१/०८/१९

उपरोक्त सम्बन्धमा यस मादी गाँड कार्यपालिकाको कार्यलय, थुमाकोडाँडा, कास्कीको वार्षिक स्वीकृत कार्यक्रम अन्तरगत वडा न. ५ मा स्वास्थ्य शाखाको स्टोर ट्रस्ट निर्माण योजना भएकोले इच्छुक निर्माण कम्पनिहरूले Bill Of Quantity मा आफुले उपलब्ध गराउन सक्ने न्युनतम दर रेट उल्लेख गरि फर्म दर्ता, करचुकाको प्रमाण पत्र (आ.व. २०८०/०८१), स्थायी लेखा न. वा मूल्य अभिवृद्धि करको प्रमाण पत्र सहित यो सूचना प्रकाशन भएको मितिले ७ (सप्त) दिन भित्र यस गाँडपालिकाको कार्यलयमा उपस्थीत भई उक्त कामको दर रेटको कोटेशन (Quotation) पेश गर्नको लागि यो सूचना प्रकाशन गरिएको छ।

नोट: उक्त कार्यको Bill Of Quantity यस मादी गाँडपालिकाको web site:- www.madimunkaski.gov.np बाट प्राप्त गर्न सकिन्छ।

तपशिल:-

| क्र.स.न. | मादी गा.पा. | कामको विवरण |
|----------|-------------|---|
| १ | वार्ड न.५ | स्वास्थ्य शाखाको स्टोर ट्रस्ट निर्माण, मादी ५ |

.....
प्रमुख प्रशासकीय अधिकारी
Kamal Prasad Gaiwani
Chief Administrative Officer



मार्गी कार्यालय प्रतिलिपि
गाँड़ कार्यालय, बिहार, भारत
शुभकालाकारकार्यालय

योजनाको नाम : स्वास्थ्य शाखाको स्टेट ट्रस्ट निर्माण - मादी ७ आ रका से केन्द्रको अवनमा
स्थान : मादी ७ ; मादी गाडी, कास्की

Bill Of Quantity

| S.N. | Description of Works | Unit | Quantity | Rate | Rate In Word | Amount | Remark |
|------|---|------|----------|------|--------------|--------|--------|
| A1 | Earthwork in excavation of all type of soil with 10 m lead and 1.5m lift | Cum | 0.54 | | | | |
| A2 | Providing and soling stone in foundation in true line and level including filling of voids by local sand all complete as per drawing, specification. | Cum | 0.135 | | | | |
| A3 | Plain Cement Concrete of grade M10 including supplying, mixing, placing, compact and cure concrete in foundation footings, tie-beams, columns, beams, lintels, slabs as per drawings, specification and instruction of site engineer. | Cum | 0.405 | | | | |
| A4 | Supply and Fitting Of Metal Work For stair,window grill etc all complete work as per drawings, specification and instruction of site engineer. | Kg | 582.3521 | | | | |
| B1 | Plain Cement Concrete of grade M15 including supplying, mixing, placing, compact and cure concrete in foundation footings, tie-beams, columns, beams, lintels, slabs as per drawings, specification and instruction of site engineer. | Cum | 0.14 | | | | |
| B2 | I Beam(ISMB150); MS pipe Truss; Purlin works for roof and post including material collection,one coat primer,fabrication and erection as per drawing all complete works as per instruction of Site Engineer. | Kg | 424.92 | | | | |

आ.व. :- २०८१/०८३
सि.न.: १८४


Kamal Prasad Gautam
Chief Administrative Officer



| B3 | MS pipe Truss;Purlin works for roof including .one coat primer,fabrication and erection as per drawing all complete works by using material available at site as per instruction of Site Engineer. | Kg | 162.84 | |
|-----|---|-----|--------|--|
| B4 | Providing and laying 26 Gauge(0.41mm)CGI color sheet over roof(Truss) all complete with leak proof joints as per instruction of site engineer. | Sqm | 78.18 | |
| B5 | Providing and laying 28 Gauge(0.28mm)Plain color sheet over roof ridge(Truss) all complete with leak proof joints as per instruction of site engineer. | Rm | 8.55 | |
| B6 | Providing and laying 28 Gauge(0.28mm)Plain color sheet over Truss portion all complete with leak proof joints as per instruction of site engineer. | Sqm | 14.57 | |
| B7 | Dismantling Of CGI Sheet Work With 10 m Lead as per specification and site engineer. | Sqm | 50.31 | |
| B8 | 150mm width 450 depth Water gutter of GI plain colour sheet with 40*3 mm pipe bracket, nutbolts, washer all complete .Including materials collection and fitting as per drawing and specifications as directed by site incharge all complete. | Rm | 17.10 | |
| B9 | Wall Gap packing Work;concrete dismantalling work all complete as per instruction of site engineer. | L/S | 1.00 | |
| B10 | PVC 110mm pipe for Gutter including fitting at site all complete as per instruction of site Engineer. | Rm | 18.00 | |
| B11 | 6"x8"x16"Concrete hollow block masonry in cement sand (1:4) mortar all complete as per instruction of site Engineer. | Sqm | 35.68 | |

Kamal Prasad Gautam
Chief Administrative Officer



Madi Rural Municipality
Office of the First Municipal Engineer
Gandaki Province, Nepal

| Supplying and Laying of 12.5mm thick cement sand plaster in (1:4) ratio on ceiling, wall,beam of good finish including supply of materials, racking the joint, wetting of surfaces & curing the work at least 7days all complete as per approved drawing, Specification and instruction of site engineer | | Sqm | 71.36 | | | | |
|--|--|-----|-------|-------------|--|--|--|
| Supplying & applying 2 coats Enamel painting in Metal Surface of approved colour with one coat of primer Painting over porperly cleaned surface at outside of building all complete as per approved drawing, Specification and instruction of site engineer. | | Sqm | 60.00 | | | | |
| Aluminium sliding window fitted with 5mm clear glass without net of section (88*38*1.1) B14 supplying and fixing in position as per approved design and specifications as instructed by site engineer all complete | | Sqm | 4.62 | | | | |
| Providing and fixing Ready Made Core Door Shutter One Side Teak and Other Side Water Proof all complete as per approved drawing, Specification and instruction of site engineer. | | Sqm | 1.74 | | | | |
| Providing and fixing Making and fixing seasoned Local Wood chaukhat Wooden size (100 mm*75 mm) all complete as per approved drawing, Specification and instruction of site engineer. | | Cum | 0.03 | | | | |
| | | | | Total | | | |
| | | | | Vat(13%) | | | |
| | | | | Grand Total | | | |

Kamal Prasad Gautam
Chief Administrative Officer