

मादी गाउँपालिका
गाउँ कार्यपालिकाको कार्यालय
थुमाकोडाँडा, कास्की
गण्डकी प्रदेश, नेपाल

आ.व.२०८१/०८२

सूचना न.०२ (प्राविधिक शाखा)

कोटेशन पेश गर्ने सम्बन्धी सूचना ।


पहिलो पटक प्रकाशित मिति: २०८१/११/०१

उपरोक्त सम्बन्धमा यस मादी गाँउ कार्यपालिकाको कार्यालय ,थुमाकोडाँडा,कास्कीको वार्षिक स्वीकृत कार्यक्रम अन्तरगत वडा न. ५ मा **Construction Of Padheri Khola Poudel Gaun Sadak** निर्माण योजना भएकोले इच्छुक निर्माण कम्पनिहरूले **Bill Of Quantity** मा आफुले उपलब्ध गराउन सक्ने न्युनतम दर रेट उल्लेख गरि फर्म दर्ता, करचुकाको प्रमाण पत्र (आ.व.२०८०/०८१),स्थायी लेखा न. वा मूल्य अभिवृद्धि करको प्रमाण पत्र सहित यो सूचना प्रकाशन भएको मितिले ७ (सात) दिन भित्र यस गाँउपालिकाको कार्यालयमा उपस्थित भई उक्त कामको दर रेटको कोटेशन (**Quotation**) पेश गर्नको लागि यो सूचना प्रकाशन गरिएको छ।

नोट:उक्त कार्यको **Bill Of Quantity** यस मादी गाँउपालिकाको **web site:- www.madimunkaski.gov.np** बाट प्राप्त गर्न सकिन्छ।


तपशिल:-

क्र.स.न.	मादी गा.पा.	कामको विवरण	लागत अनुमान
१	Ward no. 05	Construction Of Padheri Khola Poudel Gaun Sadak	NRs.4,98,974.94


प्रमुख प्रशासकीय अधिकृत
धनकुटा, कास्की


Name Of Project: Construction of Padheri Khola Poudel Gaun sadak
 Location: Madi Rural Municipality-05

SN.	Description of Works	Unit	Total Quantity	Rate	Amount (Nrs)	Remarks
A	Provisional Sum					
1	Carrying out different Additional Material laboratory tests of construction material like cement, rod, sand, aggregate, concrete cubes, bitumen etc. during construction work as per specification and direction.	PS	1.00	7,000.00	7,000.00	
2	Project description board at construction site- making, fixing all complete work as per instruction	PS	1.00	3,000.00	3,000.00	
B	General Work					
1	Earthwork in excavation of all type soils in foundation including 10m hauling distance and 1.8 m. lift all complete in approval of site engineer.	cum	37.81			
2	Supplying and Soling Stone in proper line and level with sand filling all complete as per approved drawing, Specification and instruction of site engineer.	cum	23.93			
3	Plain cement Concrete (PCC) for RCC works M 15 (1:2:4) for slab/lintels/columns/beams with approved quality of cement, sand and machine crushed stone aggregate including supply of materials, mixing, laying, curing the work at least 7 days etc all complete as per approved drawing, Specification and instruction of site engineer.	cum	22.69			



Manendra Bhandari

 Chief Administrative Officer



 १३-१३-१३

